MYSORE SPECIAL IMPROVEMENTS DIVISION.

ADVERTISEMENTS.

The 24th January 1888.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Mysore Special Improvements Division, up to 8th February 1888 for constructing an Assistant Surgeon's quarters in the western extension, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1888.

2. The plans, detailed estimate, and conditions may be seen at the Sanitary Engineer's Office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of Work.	Unit of Work.	Quantity.	Rate per Unit. Rs.	A.	P.
Assistant Surgeon's Quarters Main Building.					
Earthwork excavation and filling the same in basement	C. Yd.	171			
Filling in foundation in concrete	C. Ft.	920			
Do do with brick in chunam	do	3,474			
Superstructure, lower story with do	do	2,164			
Do upper story with do	do	2,202½			
Arch work	do	407¼			
Flooring with concrete	Sq.	6·78			
Terracing with brick in chunam	do	10·05			
Sloped Bengal terrace to oriel window projection	do	·78			
Cornice work	R. Ft.	118			
Mock ashlar work	Sq.	2·00			
Plastering with chunam in lower story	do	12·50			
Do do upper story	do	12·90			
White and color washing	do	85·40			
Burnt stone work	S. Ft.	18			
Roofing with school of arts tiles and ½" plank underneath	Sq.	13·27			
Teakwood work wrought and put up	C. Ft.	305			
Ornamental wooden finials on roof	Each.	6			
Stair case	do	1			
Doors ⅓ pannelled and ⅔ venetian complete	S. Ft.	168			
Windows iron barred ⅓ pannelled and ⅔ venetian complete	do	301½			
Glazed shutters to windows	do	301½			
Chocolate painting to doors and windows	Sq.	9·40			
Wood oil painting to wood work	do	15·00			
Earthen ware pipes	R. Ft.	52			
Wooden ladder to upper story for sweeper	Each	1			
Outhouse.					
Earthwork excavation and filling the same in basement	C. Yd.	66			
Foundation basement and superstructure with brick in mud	C. Ft.	4,026½			
Flooring with mud	S. Yd.	31			
Do with gravel to coach and stable	Sq.	2·53			
Mud plastering inside of out-houses	do	19·655			
Painting outside of out-houses	do	19·655			
White and color washing	do	39·31			
Roofing with Arcot tiles and reepers, &c.	do	13·75			
Jungle woodwork wrought and put up	C. Ft.	128			
Doors battened to out-houses	S. Ft	66			
Gate to compound	Each.	1			

4. Each tender must be accompanied by a deposit of Rs. Fifty in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for constructing an Assistant Surgeon's Quarters at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Mysore Special Improvements Division, up to 8th February 1888, for filling up Purnaiya's Nullah from Sivarampet Bridge to cross road leading Railway Station, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1888.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's office at Mysore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work.	Unit of work.	Rate per Unit.
Earth from Spoil Bank to the east of Siladar lines for filling by Tramway . .	20,000 C. Yds.	
Do from Spoil Bank beyond the Mochi Ghat for filling by Tramway . .	70,000 do	

4. Each tender must be accompanied by a deposit of Rs. fifty in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for filling up Purnaiya's Nullah from Sivarampet Bridge to cross road leading Railway Station, Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

STANDISH LEE,
Sanitary Engineer.

VACCINE DEPARTMENT.

The 23rd January 1888.

The Deputy Inspector of Vaccination, Tumkur District, will, from the 1st February 1888, inspect vaccination work in Kora, Tollal. e and Bellavi Hobbis of the Tumkur Taluk and with the aid of the vaccinators vaccinate all who are willing to undergo the vaccine operation.

C. L. LAKSHMANASAMI, L. M. S.,
Assistant Surgeon.

TUMKUR DIVISION.

UNCLAIMED MONEY.

The 21st January 1888.

A sum of Rs. 65—10—3 due to Subbanna for repairing Albur Tank, Tipetur Taluk, remains unpaid in the accounts of this Division since August 1886 and it is hereby notified that if the amount be not claimed within three months from date of this notification, it will be credited to Government.

C. T. DALAL,
Executive Engineer.